BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/15/2021-22 Dated: 15-12-2021

APPROVED TENDER SCHEDULE –'B'

Item 14

Name of Work :-Construction of CC Roads and Drains at Chikkabommasandra Cross Roads in ward no 04 Yelahanka New Town Sub Division.

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri A KUMAR REDDY	
				Rate	Rate in Words
1	Removing and refixing stone slabs of drains and pointing in CM (1:3)	Sqm	46.71	300.00	Three Hundred Only
2	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	196.50	250.00	Two Hundred Fifty Only
3	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	15.45	4000.00	Four Thousand Only
4	Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in postion, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification.	Tonne	2.10	73000.00	SeventyThree Thousand Only
	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and down size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification.	Cum	75.81	5500.00	Five Thousand Five Hundred Only
	Providing and Fixing Pre cast covering Slab 100mm thick made out of CC, jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge.	Sqm	324.69	1550.00	One Thousand Five Hundred Fifty Only

	Providing and fixing RCC precast cover slab of 230mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	26.40	3500.00	Three Thousand Five Hundred Only
8	Providing and laying plain/reinforced cement concrete of Mix 1:2:4 with OPC at 240 kgs. With 20mm and down size granite metal course aggregates at 0.878 cum and fine aggregates at 0.53 cum machine mixed, Concrete Laid in Layers not exceeding 15 cms Thick, well compcted in Foundation, Plinth and Cills, including cost of all materials, Labour, HOM curing etc., complete as per Specification.	Cum	5.52	6000.00	Six Thousand Only
9	Providing and fixing pre caste solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respecitively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of Machinery, Loading and unloading, lead and lift, transportation etc.,	Nos	613.00	500.00	Five Hundred Only
10	Painting Two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, with materials, labour complete as per specifications.	Sqm	82.80	40.00	Fourty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.